AHRI Standard 1350 (I-P)

2014 Standard for

Mechanical Performance Rating of Central Station Air-handling Unit Casings

AIR-CONDITIONING, HEATING, & REFRIGERATION INSTITUTE

we make life better™

2111 Wilson Boulevard, Suite 500
Arlington, VA 22201, USA
www.ahrinet.org
PH 703.524.8800
FX 703.562.1942

AVA Documents
Document Sharing Hub

Full document details: AHRI Standard 1350-2014 (I-P) - Mechanical Performance Rating of Central Station Air-handling Unit Casings (copy 2)

IMPORTANT

SAFETY DISCLAIMER

AHRI does not set safety standards and does not certify or guarantee the safety of any products, components or systems designed, tested, rated, installed or operated in accordance with this standard/guideline. It is strongly recommended that products be designed, constructed, assembled, installed and operated in accordance with nationally recognized safety standards and code requirements appropriate for products covered by this standard/guideline.

AHRI uses its best efforts to develop standards/guidelines employing state-of-the-art and accepted industry practices. AHRI does not certify or guarantee that any tests conducted under its standards/guidelines will be non-hazardous or free from risk.

Note: This is a new standard.
For SI ratings, see AHRI Standard 1351 (SI) – 2014.

AHRI CERTIFICATION PROGRAM PROVISIONS

Scope of Certification Program and Certified Ratings

Please refer to the most current version of the Central Station Air-handling Unit Casings Certification Program Operations Manual (OM) for the Scope of the Certification Program and Certified Ratings.

FOREWORD

This standard does not include acoustic testing or rating information for Central Station Air-handling Units (CSAHU). The unit must be tested in accordance with ANSI/AHRI Standard 260 (I-P) in order to determine actual unit sound power levels, inlet, discharge and casing radiated..

CSAHU sound levels are dependent on many factors, for example, fan type, size, and operating conditions, casing construction and casing penetrations, etc… There is often a significant interaction between the fan and the unit casing which both generates and transmits sound. The prediction of unit sound power from fan-only sound power by applying effects such as casing noise reduction can easily result in errors as large as ± 15 decibels.

Price $10.00 (M) $20.00 (NM)
Printed in U.S.A.

©Copyright 2014, by Air-Conditioning, Heating, and Refrigeration Institute
Registered United States Patent and Trademark Office

Documents
Document Sharing Hub

Full document details: AHRI Standard 1350-2014 (I-P) - Mechanical Performance Rating of Central Station Air-handling Unit Casings (copy 2)

TABLE OF CONTENTS

SECTION PAGE

Section 1. Purpose....1

Section 2. Scope....1

Section 3. Definitions....1

Section 4. Classifications....4

Section 5. Test Requirements....4

Section 6. Rating Requirements....5

Section 7. Minimum Data Requirements for Published Ratings....9

Section 8. Marking and Nameplate Data....10

Section 9. Conformance Conditions....10

TABLES

Table 1. Casing Deflection Rating Class....6

Table 2. Casing Air Leakage Rating Class....7

Table 3. Casing Thermal Transmittance Rating Class....8

Table 4. Casing Thermal Bridging Rating Class....8

FIGURES

Figure 1. Casing Air Leakage Rating Class Chart....7

APPENDICES

Appendix A. References - Normative....11

Appendix B. References - Informative....12

Appendix C. Method of Test for CSAHU Casings - Normative....13

Documents
Document Sharing Hub

Full document details: AHRI Standard 1350-2014 (I-P) - Mechanical Performance Rating of Central Station Air-handling Unit Casings (copy 2)

TABLES FOR APPENDICES

Table C1. Requirements for Test Instrumentation……. 13

FIGURES FOR APPENDICES

Figure C1. Negative Pressure CSAHU Test Apparatus ……..….14

Figure C2. Positive Pressure CSAHU Test Apparatus …….……..14

Figure C3. Positive and Negative Pressure CSAHU Test Apparatus …… 15

Figure C4. Span Measurement – Horizontal Unit……....16

Figure C5. Span Measurement – Vertical Unit……..…….....17

Figure C6. Span Measurement – Pressure Change Wall Unit……..…… ...18

Figure C7. Deflection Measurement……..……..…..19

Figure C8. Thermocouple Planes……..……..…….. ..24

Figure C9. Thermocouple Locations – Side View……..……..…….. 25

Figure C10. Thermocouple Locations – End View……..……..…….....25

Figure C11. Typical Thermocouple Mounting……..……..…….....26

Figure C12. Typical Thermocouple Shielding.……..……..…… 26

Documents
Document Sharing Hub

Full document details: AHRI Standard 1350-2014 (I-P) - Mechanical Performance Rating of Central Station Air-handling Unit Casings (copy 2)

MECHANICAL PERFORMANCE RATING OF CENTRAL STATION AIR-HANDLING UNIT CASINGS

Section 1. Purpose

1.1 *Purpose*. The purpose of this standard is to establish for Central Station Air-handling Unit Casings: definitions; classifications; test requirements; rating requirements; minimum data requirements for Published Ratings; operating requirements; marking and nameplate data; conformance conditions.

1.1.1 *Intent*. This standard is intended for the guidance of the industry, including manufacturers, designers, installers, contractors, and end users.

1.1.2 *Thermal Performance Rating Limitations.* Thermal performance ratings are intended to be used only to compare the construction of different Central Station Air-handling Units. The numerical value associated with the rating factor cannot be used to predict actual application Thermal Transmittance through casing or the risk of condensation for any specific Central Station Air-handling Unit.

1.1.3 *Review and Amendment*. This standard is subject to review and amendment as technology advances.

Section 2. Scope

2.1 *Scope*. This standard applies to Central Station Air-handling Units (CSAHU) as defined in Section 3.5.

2.2 *Exclusions.*

2.2.1 This standard does not apply to forced-circulation, free-delivery air-coolers for refrigeration, which are covered in ANSI/AHRI Standard 420.

2.2.2 This standard does not apply to unit heaters intended for free delivery of heated air or to room fan-coils as defined in ANSI/AHRI Standard 440.

2.2.3 This standard does not apply to units that have direct expansion coils incorporated by the manufacturer in a matched split system air-conditioner, or as otherwise defined in the product scope definition of the AHRI Unitary Small Equipment and Unitary Large Equipment Sections and covered in ANSI/AHRI Standard 210/240 or in ANSI/AHRI Standard 340/360.

2.2.4 This standard does not apply to unit ventilators as defined in ANSI/AHRI Standard 840.

2.2.5 This standard does not apply to variable refrigerant flow equipment as defined in ANSI/AHRI Standard 1230.

2.2.6 This standard does not apply to direct expansion (DX) dedicated outdoor air system units as defined in ANSI/AHRI Standard 920.

2.2.7 This standard does not apply to CSAHU's designed to only operate with internal casing pressure between -1.0 in H_2O and 1.0 in H_2O.

Section 3. Definitions

All terms in this document will follow the standard industry definitions in the ASHRAE Terminology website (https://www.ashrae.org/resources--publications/free-resources/ashrae-terminology), and ANSI/AHRI Standard 430 unless otherwise defined in this section.

3.1 *Casing Design Pressure.* The Central Station Air-handling Unit manufacturer's stated maximum operating pressure.

Documents
Document Sharing Hub
Full document details: AHRI Standard 1350-2014 (I-P) - Mechanical Performance Rating of Central Station Air-handling Unit Casings (copy 2)

3.2 *Casing Air Leakage Rate.* The air flow leaking through the casing of a Central Station Air-handling Unit (CSAHU) per 100 square feet of Casing Surface Area, cfm/100 ft^2. It is the ratio of the total air flow leaking through the casing measured at the Maximum Rated Pressure to the Casing Surface Area (per 100 ft^2). Where a casing at design conditions has portions of the CSAHU operating in both positive and negative pressures, the Casing Air Leakage Rate shall be determined separately for casing sections applied under positive pressure from those applied under negative pressure.

3.3 *Casing Deflection.* The deformation of the external surface of the casing, measured perpendicular to the plane of the casing surface, when the unit is subjected to a positive or negative internal air pressure, in.

3.4 *Casing Surface Area.* The total of all the exterior surface area, measured in ft^2, of the CSAHU casing calculated from the nominal external dimensions, excluding the area of the unit inlet and outlet airflow openings. The area of components which does not form part of the unit casing shall be excluded. These exclusions can include, both are not limited to: casing attachments such as base rails and/or ceiling mount structures, externally mounted devices such as dampers, louvers, hoods, and the area of the block-off plates on openings of separately tested unit sections.

3.5 *Central Station Air-handling Unit (CSAHU).* A factory-made encased assembly consisting of a fan or fans and other necessary equipment to perform one or more of the functions of circulating, cleaning, heating, cooling, humidifying, dehumidifying and mixing of air. It shall not contain a source of mechanical cooling.

3.6 *Central Station Air-handling Unit (CSAHU) Casing.* The enclosure which houses the fans, coils, filters, and other components of the CSAHU. It is generally made of metal and lined, where necessary, with material for thermal insulation and/or acoustic attenuation. It is the portion of CSAHU containing the air that is being conditioned, is exposed to the fan pressure, and separates the conditioned air from the surrounding air. This may also be referred to as the CSAHU cabinet.

3.7 *Deflection Class.* The rating class designation defined by the CSAHU's Maximum Normalized Deflection at the corresponding Rating Differential Static Pressure, specified in Table 1.

3.8 *Leakage Class.* The rating class designation that defines the maximum expected air flow leakage, cfm/100 ft^2, of the CSAHU casing operating within the interior pressure conditions specified for the total casing surface area.

3.9 *Maximum Deflection Point.* The location on the unit casing surface that has the largest Casing Deflection.

3.10 *Maximum Normalized Deflection*. The largest value of Normalized Deflection found on the Central Station Air-handling Unit, inches/inch.

3.11 *Maximum Rated Pressure for Leakage.* The absolute value of largest internal to external differential pressure across the casing at which the CSAHU casing is designed to operate. Ratings for Casing Air Leakage Rate shall include, at minimum, results at this pressure, inches H_2O.

3.12 *Negative Pressure.* Any point where the air pressure inside the CSAHU is less than the ambient air pressure, measured in inches H_2O and is always a negative value.

3.13 *Normalized Deflection*. The Casing Deflection divided by the Span, inches/inch.

3.14 *Positive Pressure.* Any point where the air pressure inside the CSAHU is greater than the ambient air pressure, measured in inches H_2O, and is always a positive value.

3.15 *Pressure Change Wall*. The plane in the CSAHU where the internal pressure changes from negative to positive.

3.16 *Published Rating.* A statement of the assigned values of those performance characteristics, under stated Rating Conditions, by which a unit may be chosen to fit its application. For Casing Air Leakage Rate and Casing Deflection, these values apply to all units of similar casing construction and type (identification) produced by the same manufacturer. For thermal performance ratings, these values only apply to the casing construction of the Standard Rating Unit. The term Published Rating includes the rating of all performance characteristics shown on the unit or published in specifications, advertising or other literature controlled by the manufacturer, at stated Rating Conditions.

3.16.1 *Application Rating.* A rating based on tests performed at Application Rating Conditions (other than Standard Rating Conditions).

Documents
Document Sharing Hub
Full document details: AHRI Standard 1350-2014 (I-P) - Mechanical Performance Rating of Central Station Air-handling Unit Casings (copy 2)

3.16.2 *Standard Rating.* A rating based on tests performed at Standard Rating Conditions.

3.17 *Rating Conditions.* Any set of ambient and operating conditions under which a single level of performance results are defined.

3.17.1 *Application Rating Conditions*. Rating conditions that are not the standard rating conditions as specified in Section 6.

3.17.2 *Standard Rating Conditions.* Rating conditions used as the basis of comparison for performance characteristics as specified in Section 6.

3.18 *Rating Differential Static Pressure.* The differential static pressure required for determining Deflection Class, in H_2O.

3.19 *"Shall" or "Should".* "Shall" or "should" shall be interpreted as follows:

3.19.1 *Shall.* "Shall" or "shall not" is used for a provision specified that is mandatory if compliance with the standard is claimed.

3.19.2 *Should.* "Should" is used to indicate provisions which are not mandatory but which are desirable as good practice.

3.20 *Span.* The shortest linear dimension of the CSAHU casing, width, height or depth, to be used in calculating the relative deflection of the corresponding surface. (Span does not transverse across a negative to positive pressure change wall. Refer to Section C5.3.6 and Figures C4, C5, and C6 for further definition of Span.)

3.21 *Standard Air.* Air weighing 0.075 lb/ft^3 which approximates dry air at 70°F and at a barometric pressure of 29.92 in Hg.

3.22 *Standard Rating Unit.* Configuration of the Standard Rating Unit is specifically defined in Section 6.1.

3.23 *Thermal Bridge.* The minimum temperature difference between the dry-bulb air temperature inside the unit and the exterior surface temperature of the CSAHU.

3.24 *Thermal Bridging Class.* The rating designation class that defines the Thermal Bridging Factor.

3.25 *Thermal Bridging Factor.* The ratio of the difference between the mean internal dry-bulb and the external casing temperature to the difference between the mean external dry-bulb air temperature and mean interior air dry-bulb temperature at the location of the Thermal Bridge. The ratio is calculated using Equation 2 in Section 6.7.

3.26 *Thermal Transmittance.* The rate at which thermal energy is transmitted through the casing with or without air leakage, $Btu/h/ft^2/°F$. (Also known as the U-value.)

3.26.1 *Thermal Transmittance without Leakage*. The rate at which thermal energy is transmitted through the casing, $Btu/h/ft^2/°F$.

3.26.2 *Thermal Transmittance with Leakage*. The rate at which thermal energy is transmitted through the casing plus the calculated rate of energy lost through air leakage at 1.0 in. H_2O, $Btu/h/ft^2/°F$.

3.27 *Thermal Transmittance Class.* The rating designation class that defines the maximum rate at which energy, $Btu/h/ft^2/°F$, will be transmitted through the CSAHU casing as a function of total casing surface area and temperature difference from interior to exterior of the unit with or without the calculated rate of energy lost through air leakage at Standard Rating Conditions.

Note: Thermal Transmittance Class may also be referred to as Thermal Transmission Class.

Documents
Document Sharing Hub
Full document details: AHRI Standard 1350-2014 (I-P) - Mechanical Performance Rating of Central Station Air-handling Unit Casings (copy 2)

3.27.1 *Thermal Transmittance Class without Leakage.* The rating designation class that defines the maximum rate at which energy, Btu/h/ft^2/°F, will be transmitted through the CSAHU casing as a function of total casing surface area and temperature difference from interior to exterior of the unit at Standard Rating Conditions.

3.27.2 *Thermal Transmittance Class with Leakage.* The rating designation class that defines the maximum rate at which energy, Btu/h/ft^2/°F, will be transmitted through the CSAHU casing as a function of total casing surface area and temperature difference from interior to exterior of the unit plus the calculated rate of energy lost through air leakage at Standard Rating Conditions.

Section 4. Classifications

4.1 *Classifications.* Equipment included within the scope of this standard shall be classified as follows:

4.1.1 *Application Type.*

4.1.1.1 Indoor
4.1.1.2 Outdoor

4.1.2 *Casing Structure.*

4.1.2.1 Low pressure (greater than 1 in H_2O and less or equal to than 4 in H_2O internal positive or negative pressure)
4.1.2.2 Medium pressure (greater than 4 in H_2O and less than 10 in H_2O internal positive or negative pressure)
4.1.2.3 High pressure (greater than or equal to 10 in H_2O internal positive or negative pressure)

4.1.3 *Casing Size.*

4.1.3.1 Small (smallest internal cross-sectional area normal to the airflow direction is less than or equal to 10 ft^2)
4.1.3.2 Medium (smallest internal cross-sectional area normal to the airflow direction is greater than 10 ft^2 and less than 60 ft^2)
4.1.3.3 Large (smallest internal cross-sectional area normal to the airflow direction is greater than or equal to 60 ft^2)

Section 5. Test Requirements

5.1 *Test Requirements*. Published Ratings for Casing Deflection, Casing Air Leakage Rate, Thermal Transmittance, and Thermal Bridging shall be verified by tests conducted in accordance with the test method described in Appendix C and at the Rating Conditions in Section 6.

5.1.1 Testing shall be performed on assembled units at a site where instrumentation is in place and test condition stability can be obtained.

5.2 *Casing Deflection.* The deflection for each section of the assembled air-handling unit casing shall be determined by testing according to the test method prescribed in Section C5.

5.2.1 The location of maximum deflection of the CSHAU Casing shall be determined and the deflection measured relative to the unpressurized condition. This test shall be performed at the standard rating pressure. The pressure shall be stable within the bounds specified in Section C5.

5.2.2 The Casing Deflection Rating shall be determined and reported using methodology outlined in Section 6.3 and Section C5.

5.3 *Casing Air Leakage Rate.* The Casing Air Leakage Rate for each section of the assembled air-handling unit shall be determined by testing according to the test method prescribed in Section C6.

Documents
Document Sharing Hub
Full document details: AHRI Standard 1350-2014 (I-P) - Mechanical Performance Rating of Central Station Air-handling Unit Casings (copy 2)

5.3.1 The amount of Casing Air Leakage Rate shall be measured. This test shall be performed at the standard rating pressure. The pressure shall be stable within the bounds specified in Section C6.

5.3.2 The Casing Air Leakage Rate shall be determined and reported using methodology outlined in Section 6.3 and Section C6.

5.4 *Thermal Transmittance.* The casing thermal heat transfer energy transmission and leakage air energy content for the assembled CSAHU shall be determined by testing according to the test method and calculations prescribed in Section C7.

5.4.1 The inside and outside the unit mean air dry-bulb temperatures shall be measured. The amount of Thermal Transmittance due to heat transfer through the unit casing walls shall be calculated based on the thermal energy input from the heaters and circulating fans inside the assembled unit and the temperature difference between inside the unit and outside the unit. The energy transfer due to airflow leakage shall be determined by measuring the leakage air flow rate and calculating the leakage air heat capacity energy content. The total energy transmittance shall be the sum of the heat transfer through the casing walls and the leakage air heat capacity. Thermal Transmittance, U, shall be calculated per the methodology outlined in Section C7.

5.4.2 Both Thermal Transmittance Classes (with and without leakage) shall be determined and reported using methodology prescribed in Section 6.4 and Section C7.

5.5 *Thermal Bridging.* The Thermal Bridging Factor shall be based on the minimum casing temperature difference between the casing exterior surface and the mean inside air temperature as determined by testing according to the test method prescribed in Section C8.

5.5.1 The Thermal Bridge location, unit exterior surface temperature, inside unit mean air temperature and the outside unit mean air temperature shall be determined per the methodology prescribed in Section C8.

5.5.2 The Thermal Bridging Factor shall be determined and reported using the methodology prescribed in Section 6.5 and Section C8.

Section 6. Rating Requirements

6.1 *Standard Rating Unit.* The Standard Rating Unit configuration shall meet the following:

6.1.1 Central Station Air-handling Unit inlet(s) and/or outlet(s):

6.1.1.1 Build unit without inlet and outlet duct openings if this is available as a standard construction option. Do not subtract any area from total exterior surface area.

6.1.1.2 If the standard unit configuration does not include an option for no duct openings, the unit shall include standard single inlet and outlet openings.

6.1.2 The entire interior of the unit must be accessible for installing instrumentation via standard service doors or standard service access panels.

6.1.3 All access points must be large enough (minimum nominal width 18 in) for person to enter and place instrumentation, including thermal sensors, heater(s), circulating fan(s). One access point between end wall and first component (either fan or coil)

6.1.3.1 One access point between first and second component or other end wall

6.1.3.2 If required, additional access points between additional components and last component and other end wall

6.1.4 Unit shall contain shipping split (if an option in the product line being rated). Additional gasket material, caulk, fasteners and other required assembly parts shall be shipped with the split unit. A copy of the assembly instructions shall be provided with the split unit.

6.1.5 Unit shall include, at minimum, a fan and a coil:

6.1.5.1 A standard size and arrangement fan(s) shall be installed, the motor(s) and drive components are not necessary if not needed for the mechanical support of the fan(s) installation.

AVA Documents Document Sharing Hub

Full document details: AHRI Standard 1350-2014 (I-P) - Mechanical Performance Rating of Central Station Air-handling Unit Casings (copy 2)

6.1.5.2 A standard size cooling coil (minimum of 65% of unit cross-section area) and drain pan. If no standard catalog selectable coil meets the minimum 65% area, use the largest standard catalog coil available for the unit.

6.2 *Standard Ratings*. Standard ratings shall be established at the Standard Rating Conditions specified in Section 6.3 for Casing Deflection, Section 6.4 for Casing Air Leakage Rate, Section 6.5 for Casing Thermal Transmittance and Section 6.6 for Thermal Bridging Factor.

6.2.1 *Casing Deflection.* Once established, ratings for Casing Deflection shall be representative of the casing construction of a range of models within a model line. For a model line which includes very small to very large units, with different panel sizes, ratings of a test unit shall only be extended to units (1) with the same casing construction as the test unit; (2) with panel Spans nominally equal to or smaller than the test unit; and (3) which are also capable of operating at the same Rating Differential Static Pressure as the test unit.

6.2.2 *Casing Air Leakage Rate.* Once established, ratings for Casing Air Leakage Rate shall be representative of the casing construction of a range of models within a model line. For a model line which includes units with a range of Casing Surface Areas, ratings of a test unit shall only be extended to units (1) with the same casing construction as the test unit; (2) with a Casing Surface Area equal to or larger than the test unit; (3) which are also capable of operating at the same Maximum Casing Design Pressure as the test unit.

6.2.3 *Thermal Performance.* Standard Ratings for Thermal Performance, Thermal Transmittance and Thermal Bridging, shall be representative of the casing construction being rated.

6.3 *Application Ratings.*

6.3.1 *Casing Deflection.* Application Ratings shall be established for Casing Deflection for pressures other than the Rating Differential Static Pressure. No Deflection Class may be reported or published for Application Ratings. For Application Ratings, users shall report the measured deflection at the tested pressure.

6.3.2 *Casing Air Leakage Rate.* Application Ratings shall be established for Casing Air Leakage for pressures other than the Casing Design Pressure. No Casing Air Leakage Class may be reported or published for Application Ratings. For Application Ratings, users shall report the measured leakage (cfm/100 ft^2) at the tested pressure.

6.3.3 *Thermal Transmittance.* Application Ratings shall be established for Thermal Transmittance. No Thermal Transmittance Class with Leakage or Transmittance Class without Leakage may be reported or published for Application Ratings. For Application Ratings, users shall report the measured thermal transmittance, U-value, at the tested conditions.

6.3.4 *Thermal Bridging.* Application Ratings shall be established for Thermal Bridging. No Thermal Bridging Class may be reported or published for Application Ratings. For Application Ratings, users shall report the measured thermal bridging factor, k_b at the tested conditions.

6.4 *Casing Deflection Rating*. The Deflection Class shall be determined from the test results, Section C5, and the Maximum Normalized Deflection at the Rating Differential Static Pressures in Table 1. For units applied in both positive and negative pressure there will be two ratings, one for positive and one for negative pressure.

Table 1. Casing Deflection Rating Class

Class Deflection, CD_x	Rating Differential Static Pressure, in H_2O	Maximum Normalized Deflection, in/in of Span
CD_1	10	0.0033 (1/300)
CD_2	8	0.0042 (1/240)
CD_3	6	0.0042 (1/240)
CD_4	4	0.0042 (1/240)
CD_5	1	≥ 0.0042 (1/240)

6.5 *Casing Air Leakage Rate.* The leakage class for Casing Air Leakage Rate shall be determined from the test results, Section C6, at the maximum Casing Design Pressure and measured leakage. The Casing Air Leakage Rate shall be calculated per Equation 1 (per ASHRAE 111/SMACNA 016) and the leakage class shall be equal or greater than the Casing

AVA Documents Document Sharing Hub

Full document details: AHRI Standard 1350-2014 (I-P) - Mechanical Performance Rating of Central Station Air-handling Unit Casings (copy 2)