ANSI/ASSP A10.23-2019

Safety Requirements for the Installation of Drilled Shafts

AMERICAN SOCIETY OF
SAFETY PROFESSIONALS

Approved American National Standard
ANSI Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019

The information and materials contained in this publication have been developed from sources believed to be reliable. However, the American Society of Safety Professionals (ASSP) as secretariat of the ANSI accredited A10 Committee or individual committee members accept no legal responsibility for the correctness or completeness of this material or its application to specific factual situations. By publication of this standard, ASSP or the A10 Committee does not ensure that adherence to these recommendations will protect the safety or health of any persons or preserve property.

Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019

ANSI®
ANSI/ASSP A10.23 – 2019

American National Standard
Construction and Demolition Operations

Safety Requirements for the Installation of Drilled Shafts

Secretariat

American Society of Safety Professionals
520 N. Northwest Highway
Park Ridge, IL 60068

Approved: April 12, 2019

American National Standards Institute

Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019

American National Standard

Approval of an American National Standard requires verification by ANSI that the requirements for due process, consensus, and other criteria for approval have been met by the standards developer. Consensus is established when, in the judgment of the ANSI Board of Standards Review, substantial agreement has been reached by directly and materially affected interests. Substantial agreement means much more than a simple majority, but not necessarily unanimity. Consensus requires that all views and objections be considered, and that a concerted effort be made toward their resolution. The use of American National Standards is completely voluntary; their existence does not in any respect preclude anyone, whether he/she has approved the standards or not, from manufacturing, marketing, purchasing, or using products, processes, or procedures not conforming to the standards. The American National Standards Institute does not develop standards and will in no circumstance give an interpretation of any American National Standard. Moreover, no person shall have the right or authority to issue an interpretation of an American National Standard in the name of the American National Standards Institute. Requests for interpretation should be addressed to the secretariat or sponsor whose name appears on the title page of this standard.

Caution Notice: This American National Standard may be revised or withdrawn at any time. The procedures of the American National Standards Institute require that action be taken periodically to reaffirm, revise, or withdraw this standard. Purchasers of American National Standards may receive current information on all standards by calling or writing the American National Standards Institute.

Published May 2019 by

American Society of Safety Professionals
520 N. Northwest Highway
Park Ridge, IL 60068
(847) 699-2929 • www.assp.org

Copyright ©2019 by American Society of Safety Professionals
All Rights Reserved.

No part of this publication may be reproduced in any form, in an electronic retrieval system or otherwise, without the prior written permission of the publisher.

Printed in the United States of America

Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019

Foreword (This Foreword is not a part of American National Standard A10.23-2019.)

This standard is one of a series of safety standards that have been formulated by the Accredited Standards Committee on Safety in Construction and Demolition Operations, A10. It is expected that the standards in the A10 series will find a major application in industry, serving as a guide to contractors, labor and equipment manufacturers. For the convenience of users, a list of existing and proposed standards in the A10 series for Safety Requirements in Construction and Demolition Operations follows.

A10.1 Pre-Project & Pre-Task Safety & Health Planning
A10.2 Safety, Health and Environmental Training (under development)
A10.3 Powder-Actuated Fastening Systems
A10.4 Personnel Hoists and Employee Elevators
A10.5 Material Hoists
A10.6 Demolition Operations
A10.7 Use, Storage, Handling and Site Movement of Commercial Explosives and Blasting Agents
A10.8 Scaffolding
A10.9 Concrete and Masonry Construction
A10.10 Temporary and Portable Space Heating Devices
A10.11 Personnel Nets
A10.12 Excavation
A10.13 Steel Erection
A10.15 Dredging
A10.16 Tunnels, Shafts and Caissons
A10.17 Safe Operating Practices for Hot Mix Asphalt (HMA) Construction
A10.18 Temporary Roof and Floor Holes, Wall Openings, Stairways and Other Unprotected Edges
A10.19 Pile Installation and Extraction Operations
A10.20 Ceramic Tile, Terrazzo and Marble Work
A10.21 Safe Construction and Demolition of Wind Generation/Turbine Facilities
A10.22 Rope-Guided and Non-Guided Workers' Hoists
A10.23 Safety Requirements for the Installation of Drilled Shafts
A10.24 Roofing – Safety Requirements for Low-Sloped Roofs
A10.25 Sanitation in Construction
A10.26 Emergency Procedures for Construction Sites
A10.27 Hot Mix Asphalt Facilities
A10.28 Work Platforms Suspended from Cranes or Derricks
A10.29 Aerial Platforms in Construction (under development)
A10.30 Installation of Anchors and Micropiles (under development)
A10.31 Digger-Derricks
A10.32 Personal Fall Protection Used in Construction and Demolition Operations
A10.33 Safety and Health Program Requirements for Multi-Employer Projects
A10.34 Public Protection
A10.35 Pressure Testing of Steel and Copper Piping Systems (under development)
A10.37 Debris Nets
A10.38 Basic Elements of a Program to Provide a Safe and Healthful Work Environment
A10.39 Construction Safety and Health Audit Program
A10.40 Reduction of Musculoskeletal Problems in Construction
A10.42 Rigging Qualifications and Responsibilities in the Construction Industry
A10.43 Confined Spaces in Construction and Demolition Operations
A10.44 Lockout/Tagout in Construction
A10.46 Hearing Loss Prevention
A10.47 Highway Construction Safety
A10.48 Communication Structures
A10.49 Control of Health Hazards

Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019

One purpose of these standards is to serve as guides to governmental authorities having jurisdiction over subjects within the scope of the A10 Committee standards. If these standards are adopted for governmental use, the reference of other national codes or standards in individual volumes may be changed to refer to the corresponding regulations.

Normative Requirements: This standard uses the single column format common to many international standards. The normative requirements appear aligned to the left margin. To meet the requirements of this standard, machinery, equipment and process suppliers and users must conform to these normative requirements. These requirements typically use the verb "shall."

> *NOTE: The informative or explanatory notes in this standard appear indented, in italics, in a reduced font size, which is an effort to provide a visual signal to the reader that this is informative note, not normative text, and is not to be considered part of the requirements of this standard; this text is advisory in nature only. The suppliers and users are not required to conform to the informative note. The informative note is presented in this manner in an attempt to enhance readability and to provide explanation or guidance to the sections they follow.*

Revisions: The A10 Committee welcomes proposals for revisions to this standard. Revisions are made to the standard periodically (usually five years from the date of the standard) to incorporate changes that appear necessary or desirable, as demonstrated by experience gained from the application of the standard. Proposals should be as specific as possible, citing the relevant section number(s), the proposed wording and the reason for the proposal. Pertinent documentation would enable the A10 Committee to process the changes in a more-timely manner.

Interpretations: Upon a request in writing to the Secretariat, the A10 Committee will render an interpretation of any requirement of the standard. The request for interpretation should be clear, citing the relevant section number(s) and phrased as a request for a clarification of a specific requirement. Oral interpretations are not provided.

No one but the A10 Committee (through the A10 Secretariat) is authorized to provide any interpretation of this standard.

Approval: Neither the A10 Committee nor American National Standards Institute (ANSI) approves, certifies, rates or endorses any item, construction, proprietary device or activity.

Appendices: Appendices are included in most standards to provide the user with additional information related to the subject of the standard. Appendices are not part of the approved standard.

Checklists: Checklists included in A10 standards may be copied and used in non-commercial settings only.

Committee Meetings: The A10 Committee meets twice per year. Persons wishing to attend a meeting should contact the Secretariat for information.

Standard Approval: This standard was processed and approved for submittal to ANSI by the American National Standards Committee on Safety in Construction and Demolition Operations, A10. Approval of the standard does not necessarily imply (nor is it required) that all Committee members voted for its approval. At the time ANSI approved this standard, the A10 Committee had the following members:

Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019

John Johnson, CSP, Chair
Steven Rank, Vice Chair
Timothy R. Fisher, CSP, CHMM, ARM, CPEA, CAE, STS, Secretary
Lauren Bauerschmidt, MS Engr, CSP, STS, Assistant Secretary
Jennie Dalesandro, Administrative Technical Support

Organization Represented	Name of Representative
3M	Raymond Mann
	Mike Boraas
AGC of America	Michael McCaffrey
	Kevin Cannon
Alliance of Hazardous Materials Professionals	Carl Heinlein, CSP, ARM, CRIS
American Insurance Services Group	Thad Nosal
	James Borchardt, CSP, CPE
American Society of Civil Engineers	John O'Connor, P.E.
	Harlan Fair, P.E.
American Society of Safety Professionals	Ken Shorter, CSP, ARM, TCDS
	A. David Brayton, CSP, CPC
American Wind Energy Association	Christopher Daniels
	Michele Myers Mihelic
APT Research, Inc.	Saralyn Dwyer
Associated Builders & Contractors, Inc.	Stephen Wiltshire, MSc
	Greg Sizemore
Barton Malow Company	Jeffrey Oliver, CSP, CHST
	Mark Haggenmaker, CHST, CCHT
Black & Veatch	John Johnson, CSP
	Jason Scollin, CSP, MS, STSC, CRIS
Building & Construction Trades Department	Chris Cain, CIH
	Gary Gustafson
Century Elevators	Paula Manning
	Eric Schmidt, P.E.
Clark Construction Group	Kurt Dunmire, CSP, CHST
Cole-Preferred Safety Consulting, Inc.	Barry Cole
Conner Strong & Buckelew	Eric Voight, CSP
	Ken Bogdan
Construction & Realty Safety Group, Inc.	Ron Lattanzio
	Frank Marino
CPWR - The Center for Construction Research & Training	Bruce Lippy, Ph.D., CIH, CSP
	Babak Memarian, Ph.D.
Eckstine & Associates, Inc.	Dennis Eckstine
	Matthew Eckstine
Edison Electric Institute	Jonathan Kerns
	Adam Frederick
Elevator Industry Work Preservation Fund	Michael Morand
	James Demmel
Ellis Fall Safety Solutions, LLC	J. Nigel Ellis, Ph.D., P.E., CSP, CPE
	John Whitty, P.E.
Engineering Systems, Inc.	David Ahearn, P.E.
	Edward Tuczak, P.E.
Fluor Corporation	Michael Weatherred, CSP
	Jim Bates, CSP
Gilbane Building Co.	Robert Hinderliter, ASP
	Thomas Trauger, CSP, ARM, CRIS

Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019

Hislop, Richard D.	Richard Hislop, P.E., CSP, ARM
	Shawn Bradfield, CSP
Independent Electrical Contractors, Inc.	Paul Dolenc
	Jerry Rivera
Innovative Safety, LLC	Daniel Paine
	Barbara Paine
Institute of Makers of Explosives	Joshua Hoffman, Ph.D., P.E.
	Susan Flanagan
International Association of Bridge, Structural, Ornamental & Reinforcing Iron Workers	Steven Rank
International Association of Heat & Frost Insulators & Allied Workers	Tim Keane
International Brotherhood of Boilermakers	Mark Garrett
	Bridget Connors
International Brotherhood of Electrical Workers	David Mullen
	Dan Gardner
International Brotherhood of Teamsters	LaMont Byrd, CIH
	Asher Tobin
International Safety Equipment Association	Cristine Fargo
	Daniel Glucksman
International Union of Bricklayers & Allied Craftworkers	David Wysocki
	Gerard Scarano
International Union of Operating Engineers	Christopher Treml
	Barbara McCabe
IUPAT	Kenneth Seal
Kiewit Power Constructors Co.	Rusty Brown, CSP
	Cody Williams, ASP
Laborers International Union of North America	Walter Jones, MS, CIH
	Travis Parsons
Lamar Advertising Company	Chuck Wigger, CSP
	Beth Phelps
Lendlease Corporation	Joel Pickering, CET, CHMM
	Michael Lentz
Liberty Mutual	Daniel Lavoie, CSP, ARM
	Stan Williams, ARM, CHST
Marsh LLC	Timothy Bergeron, CSP
Maryland Occupational Safety & Health	Mischelle Vanreusel
	Michael Daughaday, CHST
Mechanical Contractors Association of America	Peter Chaney, MS, CSP
	Dennis Langley
Miller & Long Concrete Construction	Frank Trujillo
	Alex Rodas, CHST
National Association of Home Builders	Robert Matuga
	Peter Deery, CSP, CHST
National Electrical Contractors Association	Michael Johnston
	Wesley Wheeler
National Institute for Occupational Safety & Health	Thomas Bobick, Ph.D., P.E., CSP, CPE
	G. Scott Earnest, Ph.D., P.E., CSP
National Railroad Construction & Maintenance Association	Jeffrey Meddin, CSP, CHEP, CHCM
National Roofing Contractors Association	Harry Dietz
	Thomas Shanahan
National Society of Professional Engineers	E. Ross Curtis, P.E., DFE, F.ASCE, F.NSPE
	Paul Swanson, P.E.
NESTI, Inc.	Michael Hayslip, P.E., CSP
	Jack Madeley, P.E., CSP

Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019

Operative Plasterers & Cement Masons International Association	Deven Johnson
PATMI	James Borchers Craig Pratt
Phoenix Fabricators & Erectors, Inc.	Luke Humphrey Frank Massey
Professional Safety Consultants, Inc.	Jim Lapping, MS, P.E., CSP Kathy Stieler
Safety Environmental Engineering, Inc.	Matthew Murphy
Scaffold & Access Industry Association	Ted Beville DeAnna Martin
Sheet Metal & Air Conditioning Contractors National Association	Mike McCullion, CSP, ARM Jamie Devan, CHST
SMART Union	Randall Krocka Charles Austin, MS
SPA Incorporated	Stanley Pulz, CSP, P.E.
Stock Enterprises	Steve Stock, P.E., PLS
The Association of Union Constructors	Wayne Creasap II Kathleen Dobson, CSP, CHST, STS.C
Turner Construction Company	Cindy DePrater, ALCM Abdon Friend, CSP
U.S. Army Corps of Engineers	Steven Washington
U.S. Department of Energy	Craig Schumann Maurice Haygood
United Association of Plumbers and Pipefitters	Cheryl Ambrose, CHST, OHST Rich Benkowski
United Brotherhood of Carpenters & Joiners of America	William Irwin Dale Shoemaker
United Union of Roofers, Waterproofers & Allied Workers	Richard Tessier Keith Vitkovich
West Virginia University Extension Service	Brandon Takacs, CSP, CSHM Mark Fullen, Ed.D., CSP
ZBD Constructors, Inc.	Greg Thompson, CSP Jeffrey Meddin, CSP, CHEP, CHCM

Independent Experts & Observers:

Lockton Companies	Marcus Reiter, CSP, ARM, CRIS
National Association of Tower Erectors	John P. Jones Kathryn Stieler
U.S. Department of Labor – OSHA	Scott Ketcham Eric Kampert, P.E., CSP, OHST
Warfel Construction Company	Jeffrey I. Pierce Kevin Stoltzfus

Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019

Subgroup A10.23 had the following members:

Rusty Brown, CSP, Chair
Richard Marshall, CHST, Vice-Chair
Stanley Pulz, CSP, P.E., Liaison
Michael Blanchard, ARM, CSP
Wayne Creasap, II
David Grafton
Robert Graswick
Blake Hladik
Gregory Lewis
Juan Mendiola, CHST, SMS, STSC
O'Brien Mills
Colin Perkins, CSHM
John Roma
Jason Scollin, CSP, ASP, MS, STC-C
Marshall "Bo" Walker

Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019

Contents

1. Scope, Purpose, Application and Exceptions 11
1.1 Scope 11
1.2 Purpose 11
1.3 Application 11
1.4 Exceptions 11
2. References 11
2.1 Referenced American National Standards 11
2.2 Other References 12
3. Definitions 12
4. Site-Specific Safety Plan 14
5. Site Investigation 14
6. Site Conditions 15
7. Drilling Equipment Selection 16
8. Delivery and Storage of Reinforcing Steel and Casing 16
9. Materials Handling to Points of Final Use 16
10. Power Equipment 17
11. Pressurized Lines and Hoses 17
12. Specific Drilled Shaft Installation Equipment Requirements 18
13. Concrete Placement, Pumping and Slurry Operations 20
14. Fall Protection 21
15. Casing Extraction 22
16. Drilled Shaft Entry 23
17. Working Over or Near Water 25
18. Training 27

Documents
Document Sharing Hub

Full document details: ASSP A10.23 2019