



BSI Standards Publication

Heat pump water heaters — Testing and rating for performance

Part 2: Heat pump water heaters for space heating

National foreword

This British Standard is the UK implementation of [ISO 19967-2:2019](#).

The UK participation in its preparation was entrusted to Technical Committee RHE/17, Testing of air conditioning units.

A list of organizations represented on this committee can be obtained on request to its secretary.

This publication does not purport to include all the necessary provisions of a contract. Users are responsible for its correct application.

© The British Standards Institution 2019
Published by BSI Standards Limited 2019

ISBN 978 0 580 97141 9

ICS 27.080

Compliance with a British Standard cannot confer immunity from legal obligations.

This British Standard was published under the authority of the Standards Policy and Strategy Committee on 30 June 2019.

Amendments/corrigenda issued since publication

Date	Text affected
------	---------------

INTERNATIONAL STANDARD

ISO
19967-2

First edition
2019-06-21

Heat pump water heaters — Testing and rating for performance —

Part 2: Heat pump water heaters for space heating

*Chauffe-eau à pompe à chaleur — Essais et classification des
performances —*

Partie 2: Chauffe-eau à pompe à chaleur pour le chauffage des locaux





COPYRIGHT PROTECTED DOCUMENT

© ISO 2019, Published in Switzerland

All rights reserved. Unless otherwise specified, no part of this publication may be reproduced or utilized otherwise in any form or by any means, electronic or mechanical, including photocopying, or posting on the internet or an intranet, without prior written permission. Permission can be requested from either ISO at the address below or ISO's member body in the country of the requester.

ISO copyright office
Ch. de Blandonnet 8 • CP 401
CH-1214 Vernier, Geneva, Switzerland
Tel. +41 22 749 01 11
Fax +41 22 749 09 47
copyright@iso.org
www.iso.org

Contents

Page

Foreword	iv
1 Scope	1
2 Normative references	1
3 Terms and definitions	1
4 Symbols and abbreviated terms	2
5 Installation requirements	2
5.1 Test apparatus and uncertainties of measurement	2
5.2 Test room for the airside and remote condenser	4
5.3 Installation and connection of the heat pump	4
5.4 Installation of heat pumps consisting of several parts	4
6 Setting and test conditions	4
6.1 General	4
6.2 Settings for non-ducted units	4
6.3 Setting the external static pressure difference for ducted units	5
6.4 Setting of units with integral pumps	5
6.5 Test conditions	6
7 Space heating test	7
7.1 Heating capacity test	7
7.2 Heating capacity correction	8
7.2.1 General	8
7.2.2 Capacity correction of fans for units without duct connection	8
7.2.3 Capacity correction due to indoor fan for ducted units	8
7.2.4 Capacity correction due to indoor liquid pump	8
7.2.5 Effective power input	9
7.3 Test procedure	11
7.3.1 General	11
7.3.2 Preconditioning period	11
7.3.3 Equilibrium period	11
7.3.4 Data collection period	11
7.4 Heating capacity calculation	12
7.4.1 Steady state capacity test	12
7.4.2 Transient capacity test	12
7.5 Effective power input calculation	12
7.5.1 Steady state test	12
7.5.2 Transient with defrost cycle	12
7.5.3 Transient without defrost cycle	12
8 Test results and test report	12
8.1 Data to be recorded	12
8.2 Test report	13
9 Marking	14
Annex A (informative) Maximum and minimum operation	15
Annex B (normative) Heating capacity test procedures given in 7.2 and 7.3	17
Annex C (normative) Determination of the liquid pump efficiency	21
Bibliography	25

Foreword

ISO (the International Organization for Standardization) is a worldwide federation of national standards bodies (ISO member bodies). The work of preparing International Standards is normally carried out through ISO technical committees. Each member body interested in a subject for which a technical committee has been established has the right to be represented on that committee. International organizations, governmental and non-governmental, in liaison with ISO, also take part in the work. ISO collaborates closely with the International Electrotechnical Commission (IEC) on all matters of electrotechnical standardization.

The procedures used to develop this document and those intended for its further maintenance are described in the ISO/IEC Directives, Part 1. In particular, the different approval criteria needed for the different types of ISO documents should be noted. This document was drafted in accordance with the editorial rules of the ISO/IEC Directives, Part 2 (see www.iso.org/directives).

Attention is drawn to the possibility that some of the elements of this document may be the subject of patent rights. ISO shall not be held responsible for identifying any or all such patent rights. Details of any patent rights identified during the development of the document will be in the Introduction and/or on the ISO list of patent declarations received (see www.iso.org/patents).

Any trade name used in this document is information given for the convenience of users and does not constitute an endorsement.

For an explanation of the voluntary nature of standards, the meaning of ISO specific terms and expressions related to conformity assessment, as well as information about ISO's adherence to the World Trade Organization (WTO) principles in the Technical Barriers to Trade (TBT) see www.iso.org/iso/foreword.html.

This document was prepared by Technical Committee ISO/TC 86, *Refrigeration and air-conditioning*, Subcommittee SC 6, *Testing and rating of air-conditioners and heat pumps*.

Any feedback or questions on this document should be directed to the user's national standards body. A complete listing of these bodies can be found at www.iso.org/members.html.

Heat pump water heaters — Testing and rating for performance —

Part 2: Heat pump water heaters for space heating

1 Scope

This document specifies test conditions and test procedures for determining the performance characteristics of air source heat pump water heaters for space heating with electrically driven compressors with or without supplementary heater. The purpose of this document is to rate the performance of the heat pump water heaters for space heating with no operation of any supplementary heater. In the case of heat pump water heaters for space heating consisting of several parts with refrigerant or water connections, this document applies only to those designed and supplied as a complete package.

NOTE Testing procedures for simultaneous operation for hot water supply and space heating are not treated in this document. Simultaneous means that hot water supply and space heating generation occur at the same time and can interact.

2 Normative references

There are no normative references in this document.

3 Terms and definitions

For the purposes of this document, the following terms and definitions apply.

ISO and IEC maintain terminological databases for use in standardization at the following addresses:

- ISO Online browsing platform: available at <https://www.iso.org/obp>
- IEC Electropedia: available at <http://www.electropedia.org/>

3.1

heat pump water heater for space heating heat pump

air source heat pump water heater with electrically driven compressors with or without supplementary heater for space heating purposes

3.2

heating capacity

heat given off by the unit to the heat transfer medium per unit of time

Note 1 to entry: Heating capacity is expressed in watts.

Note 2 to entry: If heat is removed by the indoor heat exchanger for defrosting, it is taken into account.

3.3

standard heating capacity

rated heating capacity under standard rating conditions as defined in [Tables 5, 6 and 7](#)

3.4 effective power input

average electrical power input of the unit within the defined interval of time obtained from:

- power input for operation of the compressor and any power input for defrosting;
- power input for all control and safety devices of the unit;
- proportional power input of the conveying devices (e.g. fans, pumps) for ensuring the transport of the heat transfer media inside the unit

Note 1 to entry: Effective power input is expressed in watts.

3.5 outdoor air

air from the outdoor environment

3.6 operating range

working range for the heat pump as specified by the manufacturer

3.7 outdoor heat exchanger

heat exchanger which is designed to remove heat from the outdoor ambient environment, or any other available heat source, or to transfer heat to it

4 Symbols and abbreviated terms

Symbol	Definition	Units
C_p	Specific heat capacity of water	$\text{kJ}/(\text{kg}\cdot\text{K})$
C_{20}	A scaling factor equal to 0,49	—
EEI	The Energy Efficiency Index equal to 0,23	—
IE	The motor efficiency level	—
P_H	Heating capacity	W
P_{hyd}	The hydraulic power of the pump	W
q	Volume flow rate	m^3/s
t	Time	s
ρ	Density of the hot water depending on the temperature at the flow meter	kg/m^3
Δp_e	The measured available external static pressure difference	Pa
Δp_i	The measured internal static pressure difference	Pa
Δt	Difference between inlet and outlet temperatures	K
η	0,3 by convention	—

5 Installation requirements

5.1 Test apparatus and uncertainties of measurement

The test apparatus shall be designed in such a way that all requirements for adjustment of set values, stability criteria and uncertainties of measurement according to this document are fulfilled.

Water systems or other heat transfer liquid systems shall be sufficiently free of entrained gas as to ensure that the measured results are not significantly influenced.

The inlet and outlet water temperatures of the heat pump are measured in the centre of the flow and as close as possible to the unit. The response time of the temperature sensor and the sampling interval shall be chosen to maintain the uncertainties in [Table 1](#).

Ducted air systems shall be sufficiently airtight to ensure that the measured results are not significantly influenced by exchange of air with the surroundings.

When performing measurements, set the highest room temperature on the unit/system control device. If in the instructions, the manufacturer indicates a value for the temperature set on the control device for a given rating condition, then this value shall be used.

Temperature and pressure measuring points shall be arranged in order to obtain mean significant values.

For free air intake temperature measurements, it is required either:

- to have at least one sensor per square meter, with not less than four measuring points and by restricting to 20 the number of sensors equally distributed on the free air surface; or
- to use a sampling device. It shall be completed by four sensors for checking uniformity if the surface area is greater than 1 m².

Air temperature sensors shall be placed at a maximum distance of 0,25 m from the free air surface.

For units consisting of a heat pump and a storage tank as a factory made unit, water inlet and outlet temperature measurements shall be taken at the inlet and outlet of this unit.

For water and brine, the density and specific heat in [Formulae \(1\), \(2\) and \(3\)](#) shall be determined in the temperature conditions measured near the volume flow measuring device.

For inverter type control units, the setting of the frequency shall be done for each rating condition. The manufacturer shall provide in the documentation information instructions on how to obtain the necessary data to set the required frequencies. If skilled personnel with knowledge of control software is required for the start of the system, the manufacturer or the nominated agent should be in attendance when the system is being installed and prepared for tests.

The uncertainties of measurement shall not exceed the values specified in [Table 1](#). Additionally, the heat capacity measured on the liquid side shall be determined within a maximum uncertainty of 5 % independently of the individual uncertainties of measurements including the uncertainties on the properties of the fluid.

Table 1 — Uncertainties of measurement

Measured quantity	Unit	Uncertainty
Liquid		
Temperature	°C	±0,15 K
Temperature difference	K	±0,15 K
Volume flow	l/min	±1 %
Static pressure difference	kPa	±1 kPa (≤20 kPa) ±5 % (>20 kPa)
Concentration (for brine)	%	2 %
Air		
Dry bulb temperature	°C	±0,2 K
Wet bulb temperature	°C	±0,4 K
Volume flow	m ³ /h	±5 %
Static pressure difference	Pa	±5 Pa (ΔP ≤ 100 Pa) ±5 % (ΔP ≥ 100 Pa)

Measured quantity	Unit	Uncertainty
Electrical quantities		
Electric power	W	±1 %
Electrical energy	kWh	±1 %
Voltage	V	±0,5 %
current	A	±0,5 %

5.2 Test room for the airside and remote condenser

The size of the test room shall be selected to avoid any resistance to air flow at the air inlet and air outlet orifices of the test object. The air flow through the room shall not be capable of initiating any short circuit between the two orifices, and therefore the velocity of air flow at these two locations shall not exceed 1,5 m/s when the test object is switched off.

Unless otherwise stated by the manufacturer, the air inlet and air outlet orifices shall not be less than 1 m from the surfaces of the test room.

Any direct heat radiation (e.g. solar radiation) onto heating units in the test room onto the heat pump or onto the temperature measuring points shall be avoided.

5.3 Installation and connection of the heat pump

The heat pump shall be installed and connected for the test as recommended by the manufacturer in the installation and operation manual. If a back-up heater is provided in option or not, it shall be switched off or disconnected to be excluded from the testing. Temperature and pressure measuring points shall be arranged in order to obtain representative mean values.

5.4 Installation of heat pumps consisting of several parts

In the case of heat pumps consisting of several refrigeration parts (split heat pumps), the following installation conditions shall be complied with for the tests:

- each refrigerant line shall be installed in accordance with the manufacturer's instructions; the length of each line shall be between 5 m and 7,5 m;
- the lines shall be installed so that the difference in elevation does not exceed 2,5 m;
- thermal insulation shall be applied to the lines in accordance with the manufacturer's instructions;
- unless constrained by the design, at least half of the interconnecting lines shall be exposed to the outdoor conditions with the rest of the lines exposed to the indoor conditions.

6 Setting and test conditions

6.1 General

Set points for internal control equipment of the unit, i.e. thermostats, pressure switches or mixing valves, shall be set to the values as stated in the installation and operating instructions.

If several set points or a range are stated, the manufacturer shall indicate the one to be used for the tests.

6.2 Settings for non-ducted units

For non-ducted units, the adjustable settings, i.e. louvers and fan speed, shall be set according to the installations and operating instructions.