

SIGNET Automatic recloser

'H' Examination

Visual Inspection

- a) Check the security of all connections to the VCB.
- b) Check the security of all connections to the changeover contactors.
- c) Check all internal cables for signs of fraying or degradation of insulation.
- d) Check that the Rogowski Current Sensor connector to the VCB is secure.
- e) Check that all connectors on the Control Electronics assembly are securely inserted.

Functional Tests

- a) In accordance with the requirements of the procedure contained within the appropriate Operating and Maintenance Manual, conduct functional testing.
- b) Record results.

Routine Battery Change

- a) Replace all three batteries within the MMI panel of the signet.
- b) In accordance with the requirements of the procedure contained within the appropriate Operating and Maintenance Manual, perform 'Replace Batteries' routine with Signet Maintenance Manager.

NOTE Allow a period of 3 minutes to elapse if batteries are to be changed immediately after the signet becomes de-energised.

End



Ref: **NR/FP C101**
Issue: **4**
Date: **03 September 2011**
Page: **2 of 2**

SIGNET Automatic recloser

This page is intentionally blank

Document Information: 03/27/2016 20:40:53 MDT