

Ref:	NR/L2/CTM/012/018
Issue:	1
Date:	06 March 2010
Compliance date:	04 September 2010

NR/L2/CTM/012/018 Competence & Training in Signal Engineering

Sig 18: Undertake corrective and preventative maintenance of relay based interlocking.

1 Purpose.

The purpose of this competence standard is to define the competence requirements for persons required to undertake corrective maintenance of relay based interlocking.

2 Scope.

This competence standard applies in all circumstances where any person is required fault or test relay based interlockings on Network Rail managed infrastructure.

The level and extent of responsibility will include their own safety and that of others who might be affected by their work. The person will be expected to refer to others for authorisation when required, will be responsible for the implementation of the instructions and will work within set procedures and specifications. The person is responsible for the quality of their completed work.

This competence standard shall be used to assess the competence of people faulting any of the following relay based interlockings:

- | | |
|--|---|
| <ul style="list-style-type: none"> • Free wired 850 & Pre 850 spec. • Western Region Geographical. • GEC & SGE Geographical. • Scottish Region Geographical • Western Region Geographical | <ul style="list-style-type: none"> • Westinghouse Geographical Mk 1. • Westinghouse Geographical Mk 2. • Westinghouse Geographical Mk 3 & 3A. • Westinghouse Geographical Mk 4A |
|--|---|

3 Competence Standard.

This Competence Standard comprises four elements.

Element 1 Carry out planned maintenance of relay based interlocking.

Element 2 Diagnose faults in relay based interlocking.

Element 3 Restore relay based interlocking to operational condition by repair.

Element 4 Conduct specified testing of relay based interlocking, analyse and interpret the results.

The first element is concerned with the safe completion of planned maintenance in accordance with instructions. The second and third elements are concerned with the safe completion of locating, diagnosing and repairing faults. The fourth element deals with testing of the equipment and analysing and interpreting the results to make sure that the equipment meets its operating requirements.

To prove competence in this unit, the person shall demonstrate their ability to complete work in accordance with instructions, locate, diagnose and repair faults associated with inability to set a single or multiple routes on the interlocking, call points, clear a signal, or cancel a route caused by failure in the push button, route

Ref:	NR/L2/CTM/012/018
Issue:	1
Date:	06 March 2010
Compliance date:	04 September 2010

calling/locking route checking failure or cancelling circuitry and complete the appropriate testing. The person will have to show they can follow recording, reporting and escalation procedures.

4 Assessment.

4.1 Initial Assessment.

Where the equipment is new to the person's area of responsibility the evidence requirements defined in each element apply. Due to the difficulty in collecting evidence by observation in the workplace the primary source will be from training except for element one where some performance evidence shall be collected as described in the element.

Performance evidence may come from a variety of sources and will include evidence derived from surveillance (direct observation) by an approved assessor. Evidence will also include detailed questioning and may additionally be supported by performance reports from the person's line manager.

4.2 Re-Assessment

Re-assessment shall be completed in accordance with the applicable requirements set out in 7.2 of NR/L2/CTM/012.

4.3 Knowledge Evidence that is common to the whole unit.

You shall have knowledge and understanding of:

- a) Engineering specifications associated with specific type of relay based interlocking.
- b) How the maintenance, faulting, repair and testing activity may affect the safe operation of the railway.
- c) What procedures need to be followed to demonstrate operational and personal safety is maintained during the work.
- d) How the relay based interlocking is designed to function under normal operating conditions.
- e) What each of the component parts contributes to the operation of the system.
- f) What stages apply to setting and cancelling a route and what conditions shall be met before a route can be set or cancelled.
- g) How fault finding aids relating to push button circuitry affect the rest of the interlocking.
- h) What the principle differences are between free wired and geographic interlockings.
- i) What tools are required to complete the work and what equipment calibration is required.
- j) What maintenance authorisation procedures are and limits of your responsibility and authority.
- k) What equipment operating and care and control procedures are applicable to relay based interlocking.
- l) What procedures apply to taking the equipment out of operational service and what procedures apply to handing back the equipment to operational service.
- m) Maintenance reporting documentation and control procedures.

Copyright Network Rail

Ref:	NR/L2/CTM/012/018
Issue:	1
Date:	06 March 2010
Compliance date:	04 September 2010

- n) Reporting lines and escalation procedures.
- o) Industry protocols relating to communication important safety information.

Copyright Network Rail