

Ref:	NR/L2/SIG/11201/ Mod X24
Issue:	2
Date:	02/06/2012
Compliance date:	01/12/2012

Level 2

Signalling Design: Module X24 – Level Crossings: On Call Barriers

Endorsement and Authorisation

For endorsement and authorisation, please refer to
NR/L2/SIG/11201

This document is the property of Network Rail. It shall not be reproduced in whole or part nor disclosed to a third party without the written permission of Network Rail.

© Copyright 2012 Network Rail.

Uncontrolled copy once printed from its electronic source.

Published and Issued by Network Rail, Kings Place, 90 York Way, London. N1 9AG.



Ref:	NR/L2/SIG/11201/ Mod X24
Issue:	2
Date:	02/06/2012
Compliance date:	01/12/2012

Issue record

Issue	Date	Comments
1	December 2011	First Issue
2	June 2012	Second Issue

Compliance

This Network Rail standard is mandatory and shall be complied with by Network Rail and its contractors if applicable from 03/12/2011.

When this standard is implemented, it is permissible for all projects that have formally completed GRIP Stage 3 (Option Selection) to continue to comply with the issue of any relevant Network Rail standards current when GRIP Stage 3 was completed and not to comply with requirements contained herein, unless stipulated otherwise in the scope of this standard.

Disclaimer

In issuing this document for its stated purpose, Network Rail makes no warranties, express or implied, that compliance with all or any documents it issues is sufficient on its own to ensure safe systems of work or operation. Users are reminded of their own duties under health and safety legislation.

Supply

Copies of documents are available electronically, within Network Rail's organisation. Hard copies of this document may be available to Network Rail people on request to the relevant controlled publication distributor. Other organisations may obtain copies of this document from IHS. Tel: 01344 328039.

Ref:	NR/L2/SIG/11201/ Mod X24
Issue:	2
Date:	02/06/2012
Compliance date:	01/12/2012

Contents

1 “ON CALL” BARRIERS (MCB-OC)	4
2 METHOD OF OPERATION	6
3 CONTROLS AND INDICATIONS.	8
4 ON-CALL UNIT	8
5 CCTV ARRANGEMENTS	9
6 LOCAL CONTROL UNIT.	10
7 HAND OPERATION.	10
Figure 1 – MCB-OC General Arrangements	4
Figure 2 – MCB-OC On Call Unit With Suggested Signage	6

Copyright Network Rail

Ref:	NR/L2/SIG/11201/ Mod X24
Issue:	2
Date:	02/06/2012
Compliance date:	01/12/2012

1 “ON CALL” BARRIERS (MCB-OC)

1.1 GENERAL DESCRIPTION

1.1.1 Where the number of trains exceeds the numbers of vehicles passing over the crossing it reduces the workload of signallers if the normal position of the barriers is lowered across the road. Such crossings require a means for a user at the crossing to inform the signaller that they require to cross. This gives rise to the name for this version of an MCB which shall be known as an “On Call Barrier” or “MCB-OC”.

1.1.2 This section sets out minimum requirements for an MCB-OC crossing.

1.1.3 An MCB-OC does not require Road traffic Lights (RTL’s), or the camera column associated with a MCB-CCTV crossing. However RTL’s and/or MCB-CCTV camera systems (complete with any appropriate floodlighting), may be provided if it is appropriate for other reasons.

NOTE One reason may be to make the operation of the crossing similar to existing MCB-CCTV types in the same signal box or workstation. If the extra facilities are provided, then they shall follow appropriate requirements of the MCB and MCB-CCTV sections but the RTL’s shall extinguish and audible warnings shall silence when the barriers become fully lowered.

1.1.4 This type of crossing shall not be provided where there are more than two tracks, or the maximum permitted speed is greater than 90mph, or where there is a station adjacent.

1.1.5 The general arrangement of a MCB-OC crossing shall comprise a pair of barriers together with a set of wicket gates for pedestrians. The barriers shall normally be maintained lowered and closed across the road. An “On-Call” unit comprising a plunger, indication and signs detailing its use shall be provided so that users can inform the signaller when they require to cross the railway. No RTL’s shall be provided. A CCTV system shall be provided with a full view of the crossing area plus sufficient view of the road approaches so that the remote operator can safely lower the barriers.




Figure 1 – MCB-OC General Arrangements

1.1.6 Two barriers shall be provided to close the road. Where wicket gates are