

The following information is associated with Network Rail Standard:
[NR/L3/CIV/140/130N](#) Issue 1

Additional Content Access

Click the links below to access non PDF related content associated with this standard.

Word Document

- [NR/L3/CIV/140/130N](#)

If you have any questions, or need assistance, please contact [IHS Support](#)

Information accessed via the links above is the property of the Copyright holder

IHS Additional Content Page

RAILTRACK PLC

MODEL CLAUSES FOR SPECIFYING CIVIL ENGINEERING WORKS

SECTIONS 130 - 134

**Inspection of New Steelwork, Precast
Concrete, Protective Treatment and
Waterproofing**

ISSUE NO. 1 REVISION A

RT/CE/C/008/130N

Page 1 of 26

Date: 31 January 1997

Amendments

Amendments and additions since the previous issue are marked by a vertical line in the right hand margin.

© Railtrack PLC 1997

This document is the property of Railtrack PLC. It shall not be reproduced in whole or in part without the written permission of the publisher for use external to Railtrack.

Published by

Director Civil Engineering,
Railtrack PLC,
Eastside Offices
King's Cross Station
London N1 9AP

Controlled document

No:.....

Compiled by: Owen Williams Railways
Meridian
85 Smallbrook Queensway
Birmingham B5 4HY

Edited by: Keith Ross
Structures Standards Engineer
Civil Engineering Directorate
King's Cross

Approved by: Model Clauses (Civil Engineering)
Committee on 23 April 1997

Signature:
for Director, Civil Engineering

John Horsler
Civil Engineer, Structures Compliance
Chairman Model Clauses (Civil Engineering)
Committee

SECTION 130

INSPECTION OF NEW STEELWORK, PRECAST CONCRETE, PROTECTIVE TREATMENT AND WATERPROOFING

SECTION CONTENTS

Page

This table of contents does not form part of the Specification

NOTES TO SPECIFIER

I 30.1	Generally	4
I 30.2	Application of Clauses	4
I 30.3	Reference to other Sections	4
I 30.4	Organisation of Sections	4

SPECIFICATION CLAUSES

SECTION 130

GENERAL REQUIREMENTS FOR INSPECTION

I 30.001	Definitions	5
I 30.002	Scope of the Inspection	5
I 30.003	Checking of fabrication drawings	6
I 30.004	Checking of method statements	6
I 30.005	Competency of Inspector(s)	7
I 30.006	Inspection procedures and plan	7
I 30.007	Inspection schedule	7
I 30.008	Location of inspections	8
I 30.009	Inspection reports	9

SECTION 131

INSPECTION OF NEW STEELWORK

I 31.001	Materials verification	9
I 31.002	Preparation verification - welding	10
I 31.003	Preparation verification - dimensional	10
I 31.004	Process specification verification	11
I 31.005	Process verification	12
I 31.006	Completed item verification generally	13
I 31.007	Completed item verification: trial erection	14

SECTION 132

INSPECTION OF PRECAST CONCRETE

I 32.001	Materials verification	15
I 32.002	Preparation verification	15
I 32.003	Process specification verification	16
I 32.004	Process verification	16
I 32.005	Completed item verification generally	17
I 32.006	Completed item verification: trial erection	17

SECTION 133	INSPECTION OF PROTECTIVE TREATMENT	
	I33.001 Materials verification	18
	I33.002 Preparation verification	19
	I33.003 Process specification verification	19
	I33.004 Process verification	19
	I33.005 Completed item verification	20
SECTION 134	INSPECTION OF WATERPROOFING	
	I34.001 Material verification	20
	I34.002 Preparation verification	21
	I34.003 Process specification verification	21
	I34.004 Process verification	21
	I34.005 Completed item verification	22
APPENDIX	I30A Visit Report	23
REFERENCES	<i>Railtrack Line Standards</i>	26

SECTION 130

**INSPECTION OF NEW STEELWORK, PRECAST CONCRETE,
PROTECTIVE TREATMENT AND WATERPROOFING**

NOTES TO SPECIFIER:

These notes do not form part of the Specification.

Generally **130.1** *Sections 130 - 134 have been written for use in a Specification for inspection only contracts between Railtrack and an inspection company and assumes a separate site management contract.*

Where inspection duties are to be included within an overall contract for site management, references to the site management contractor should be changed to 'Employer's Representative'.

**Application of
Clauses** **130.2** *The Model Clauses have been written with primarily for bridge works. However, the Clauses may be applied to the inspection of other structures, including precast troughing units and sleepers, where the materials and workmanship specification is similar to that used for bridge works.*

**Reference to other
Sections** **130.3** *This Section is to be used in conjunction with Section 10: General and other relevant sections within the Contract. Reference should also made to the materials and workmanship specification for the Works to be inspected.*

**Organisation of
Sections** **130.4** *The document is divided into five Sections to cover General Requirements for Inspection, Steelwork, Precast Concrete, Protective Treatment and Waterproofing.*

Steelwork *Section 131 has been written with reference to BS 5400 and the materials and workmanship requirements specified in Sections: 70, 73, 79 and 90. If the items to be inspected are of a minor nature the Clauses may be simplified by the Specifier.*

Precast Concrete *Section 132 has been written with reference to the materials and workmanship requirements specified in Sections: 70, 71 Precast Piles and Section 80: Structural Concrete.*

**Protective
Treatment** *Section 133 has been written with reference to the material and workmanship requirements specified in Sections 170 - 176: Protective Treatment. It takes account of both shop and site applied coatings.*

Waterproofing *Section 134 has been written with reference to the materials and workmanship requirements specified in Sections 110 - 115: Waterproofing.*

SECTIONS
130 - 134

**INSPECTION OF NEW STEELWORK, PRECAST
 CONCRETE, TREATMENT AND WATERPROOFING
 PROTECTIVE**

SECTION 130

GENERAL REQUIREMENTS FOR INSPECTION

Definitions

130.001

The following definitions shall apply:

- (i) Contractor shall mean the company or person carrying out the construction of the Works, including any fabrication or manufacturing sub-contractor,
- (ii) Inspector shall mean the competent person who is to carry out the inspection of the Works,
- (iii) Non compliance shall mean a deviation from the requirements of the contract for the works, including but not limited to the specification, contract drawings, agreed methods of working or procedures etc,
- (iv) Site Management contractor shall mean the contractor employed to provide management services for the construction of the works,
- (v) Verification shall mean the activities required to ensure that a process output meets the specification or other input requirements,
- (vi) Works shall mean the structure, including its materials and components, to be inspected.

SEE NOTES TO
 SPECIFIER

NOTE TO SPECIFIER

Should there be no Site Management contractor, references in this Specification to 'Site Management contractor' should be changed to 'Employer's Representative'. In order to differentiate between the Contractor in the Contract which is written in the Model Clauses with a capital 'C', as the Site Management contractor is not the same company or person, 'contractor' in the Site Management contractor is written with a small 'c'.

(130.001)

**Scope of
 Inspection**

130.002

The Works to be inspected comprise :

*Insert details of Works
 to be inspected*

!C!

- (i)
-
-

!C!

- (ii)
-
-

Specification
Inspection of New Steelwork, Precast Concrete,
Protective Treatment and Waterproofing

IC! (iii)
.....
.....

IC! The Inspector shall verify that the Works have been carried out in accordance with the specification for materials and workmanship and the contract drawings **!CHECK!** for the Works. Any non compliances with the specification for materials and workmanship or the contract drawings shall be identified and reported to the Site Management contractor or the Employer's Representative as applicable.

NOTE TO SPECIFIER

The Specification for the Works may be supplied to the Inspector at Tender stage or as an Appendix to the Contract Documents, separately, or at a later date.

The Inspector shall not accept or reject work on behalf of the Site Management contractor or the Employer's Representative.

The Inspector shall provide the Site Management contractor when required with advice on matters relating to materials and workmanship, programme, method statements or any other matter relating to the Works in order that the specification for the Works may be met.

(130.002)

**Checking of
fabrication
drawings**

130.003
IC!

The Inspector shall check the fabrication drawings and report all errors, omissions, and discrepancies with the specification or contract drawings shown on the fabrication drawings or any other matter relating to the Works which might prevent compliance with the specification for the Works. The Inspector shall not approve fabrication drawings.

NOTE TO SPECIFIER

Checking of fabrication drawings may be allocated to the designer.

(130.003)

**Checking of
method
statements**

130.004

The Inspector shall check method statements for the fabrication or manufacture of the Works, and shall identify and report bad practices proposed to be used in respect of the technical aspects of the proposed method statements and any incorrect sequences of fabrication or any other matter relating to the Works which might prevent compliance with the specification for the Works. The Inspector shall not approve method statements.

(130.004)

**Competency of
Inspector(s)**

130.005
IC!

The curriculum vitae of the Inspector(s) shall be submitted with the Tender **!CHECK!** and shall include, in addition to criteria considered relevant by the Contractor, details of the Inspector's experience of:

- (i) inspection of works for railway construction,
- (ii) inspection of works of a similar nature,
- (iii) certification of competency in inspection and testing procedures,

Specification
Inspection of New Steelwork, Precast Concrete,
Protective Treatment and Waterproofing

Insert any other details required **IC!** (iv)

IC! (v) professional qualifications.
 (130.005)

**Inspection
 procedures and
 plan**

130.006 The procedures used for the Inspection shall be approved to BS EN ISO 9002 or BS EN ISO 9003 by a body accredited by the United Kingdom Accreditation Service (UKAS) or other quality systems that can be demonstrated to the Employer's Representative to be equivalent.

IC! The draft inspection plan shall be submitted with the Tender, **ICHECK!** and shall include:

- (i) details of Inspector(s) to be used,
- (ii) schedule of inspections and checks related to items to be inspected,
- (iii) outline checklists,
- (iv) reporting procedure,
- (v) format for inspection reports.

IC! Within 14 days **ICHECK!** of the award of the Contract, the final inspection plan shall be issued for the consent of the Site Management contractor.
 (130.006)

**Inspection
 schedule**

130.007 Assuming a manufacturing period of weeks, the inspection schedule shall allow for the minimum number of visits shown in Table 130/I. **IC!** **ICHECK!**

SEE NOTES TO
 SPECIFIER
 General Preliminary

Steelwork

Concrete

Table 130/I	
Item	No. of Visits
Fabrication Drawings	-
Works Inspection	1
Equipment Inspection	1
Materials and Welding Procedures Audit	1
Materials Inspection	1
Preparation Audit	1
Preparation Inspection	1
Process Inspection - Welding	1
Process Inspection - Other	1
Completed Item Checks	1
Remedial Works	1
Materials Audit	1
Formwork Fabrication	2
Reinforcement Fixing	1
Prior to Casting	1
Casting	10
Stripping of Formwork	1
Curing	1
Completed Item Checks	1