

The following information is associated with Network Rail Standard:
NR/L3/CIV/140/185N Issue 1

Additional Content Access

Click the links below to access non PDF related content associated with this standard.

Word Document

- [NR/L3/CIV/140/185N](#)

If you have any questions, or need assistance, please contact [IHS Support](#)

Information accessed via the links above is the property of the Copyright holder

IHS Additional Content Page

RAILTRACK PLC

**MODEL CLAUSES FOR SPECIFYING
CIVIL ENGINEERING WORKS**

SECTIONS 185 - 186
Track Drainage

ISSUE NO. 1 REVISION B

RT/CE/C/008/185N
Page 1 of 19

Date: 31 January 1997

Amendments

Amendments and additions since the previous issue are marked by a vertical line in the right hand margin.

© Railtrack PLC 1997

This document is the property of Railtrack PLC. It shall not be reproduced in whole or in part without the written permission of the publisher for use external to Railtrack.

Published by

Director Civil Engineering,
Railtrack PLC,
Eastside Offices
King's Cross Station
London N1 9AP

Controlled document

No:.....

Submitted by: Keith Ross
Structures Standards Engineer
Civil Engineering Directorate
King's Cross

Approved by: Model Clauses (Civil Engineering)
Committee 19 March 1997

Signature:
for Director, Civil Engineering

John Horsler
Civil Engineer, Structures Compliance
Chairman Model Clauses (Civil Engineering)
Committee

Copyright Network Rail
Provided by IHS under license with Network Rail
No reproduction or networking permitted without license from IHS

SECTIONS 185 - 186

TRACK DRAINAGE

SECTION CONTENTS

Page

This table of contents does not form part of the Specification

NOTES TO SPECIFIER

185.1	Track drainage generally	3
185.2	Wooden catchpit covers	3

SPECIFICATION CLAUSES

SECTION 185

TRACK DRAINAGE

185.001	Design of track drainage systems generally	4
185.002	Design of catchpits	5
185.003	Construction of track drainage generally	5
185.004	Definitions	5
185.005	Drain pipes	6
185.006	Unplasticised polyvinyl-chloride (UPVC) pipes	7
185.007	Thermoplastic pipes	7
185.008	Perforated corrugated steel pipes	8
185.009	Geotextiles	8
185.010	Granular fill materials	8
185.011	Precast concrete units for catchpits	8
185.012	Laying of drain pipes generally	9
185.013	Joints generally	9
185.014	Channel collector drains	9
185.015	Piped lineside collector drains	10
185.016	Track cross drains	11
185.017	Piped lineside carrier drains	12
185.018	Geotextiles in drainage systems	12
185.019	Catchpits to collector drains	13
185.020	Catchpit covers	14
185.021	Manholes to carrier drains	15
185.022	Connections to existing drainage system	15
185.023	Outfalls	15
185.024	Testing of carrier drains	16
185.025	Redundant drains	16
185.026	Records	16
185.027	Drainage system to be left clean	16

SECTION 186

MAINTENANCE OF TRACK DRAINAGE

186.001	Inspection of track drainage	17
186.002	Channel drains	17
186.003	Catchpits	17
186.004	Collector and carrier drains	17

REFERENCES

British Standards	19
Railtrack Line Standards	19

SECTIONS 185-186

TRACK DRAINAGE

NOTES TO SPECIFIER:

These notes do not form part of the Specification.

Track drainage generally	185.1	<i>Recommendations for the design, construction and installation are given in Railtrack Line Standard RT/CE/C006.</i>
---------------------------------	--------------	---

Wooden catchpit covers	185.2	<i>Where wooden catchpit covers are discovered or known to exist, such covers should be replaced, since such covers when rotten may collapse when walked upon.</i>
-------------------------------	--------------	--

Regrettably an incident has occurred whereby such a cover, hidden under cess track ballast, was trodden upon and it collapsed. The unfortunate person was thrown onto the electrified rail and electrocuted.

SECTION 185

TRACK DRAINAGE

Design of track drainage systems generally

185.001

!
!

Where not shown on the Contract Drawings, **!CHECK!** drainage systems for the tracks at the locations detailed in the relevant Particular Specification **!CHECK!** shall be designed by competent Contractor's personnel to suit the particular features of the Site, and in accordance with the requirements of Railtrack Line Standard RT/CE/S102.

!
!

The length and location of the track(s) to be drained, and any requirements to ensure compatibility with the existing drainage system, where applicable, shall be as specified in the relevant Particular Specification. **!CHECK!**

Track drainage shall be designed to collect and convey from the track and its immediate vicinity, water arising from rainfall or run off from cuttings, adjacent land or springs, and to minimise the risk of the stability of the track being affected by standing or flowing water.

NOTE TO SPECIFIER

Where a drainage system is required at locations where oil leakage occurs or may occur regularly, such as where diesel engines idle, consideration should be given to the specification of oil interceptors within the track drainage system.

This Clause should only be included where the Contract includes the design of track drainage

!
!

A scheme drawing and details of the proposed material for the drain pipes and the proposed form of construction shall be provided with the Tender. **!CHECK!**

!
!

Details of the proposed drainage scheme shall be submitted to Railtrack for approval in principle using Form A based on the model in Appendix C. **!CHECK!**

The position, size, level and materials of construction and condition of the existing drainage systems external to Railtrack owned land to which the proposed drainage shall be connected and any other information pertinent to carrying out the design shall be determined by the Contractor.

NOTE TO SPECIFIER

The above paragraph assumes Railtrack will provide information on existing drainage systems within Railtrack owned land.

(185.001)

Design of catchpits **185.002**

!
!

Where a catchpit is proposed to be constructed within ground subject to railway variable loading, the catchpits shall be designed and the design checked as specified in the Contract **!CHECK!** to ensure that the catchpit can resist, without deformation or collapse, the Permanent Loads and where applicable the surcharge due to RU type loading acting at the underside of the sleepers as defined in BS 5400: Part 2.

!
!

A completed Certificate of Design and Checking (Form B) based on the model shown in Appendix C **!CHECK!** shall be provided for the catchpit design, a minimum 13 weeks **!CHECK!** before construction of the catchpits is programmed to commence.

NOTE TO SPECIFIER

For catchpits design, the design check should be category III, and specified accordingly in the Technical Workslope Data Sheets.

Where a catchpit is produced to a standard design, evidence of the structural adequacy as detailed in the manufacturer's literature shall be acceptable, and the design check may be limited to confirmation that the catchpit design strength can resist the design loading specified above.

(185.002)

Construction of track drainage generally

185.003 Track drainage shall be constructed in accordance with Railtrack Line Standard RT/CE/SI02 as qualified or amended by the following Clauses.**!CHECK!**

!C!

Excavations for track drainage shall be carried out in accordance with Section 51: Excavations.**!CHECK!**

!C!

(185.003)

Definitions

185.004 The following definitions shall apply:

- (i) 'Collector drain' shall mean a drain designed to collect water from the surface and/or from the surrounding ground continuously along its length through open joints or perforations, and which may be laid at the surface, or below the surface of the ground. (Note - "continuously" is taken to include pipes up to 1200 mm long which afford access only at the joints).

Such drains also act as a carrier for the water collected and may additionally be connected to a separate carrier drain.

- (ii) 'Carrier drain' shall mean an impervious drain designed to carry water which is laid with joints sufficiently tight to prevent the ingress or egress of water and to prevent the ingress of fine soil particles.

- (iii) 'Catchpit' shall mean a chamber provided at intervals in the run of a piped drain to give access from the surface for cleaning out the pipe and including a sump to collect silt.

- (iv) 'Outfall' shall mean the place at which a drainage system discharges into another drainage system or watercourse.

(185.004)