

Task Risk Control Sheet

Painting

RCS No: NR/L3/MTC/RCS0216/PR09
Issue: 2

Key Risks !

- Fire/Explosion
- Asphyxia / Poisoning
- Falling Materials
- Falls from Height
- Slips, Trips and Falls

Personnel Involved

E&P	
S&T	
Track	
Off Track	
Property	✓

Tools / Equipment

Hand Tools

Ladders

Scaffold

Plant

Gas Burner

Compressor

Task Risks	Controls	Implemented By
Fire / Explosion	<ul style="list-style-type: none"> • All paints, varnishes and solvent shall be handled as per COSHH data sheets. • Alternatives to harmful paints/varnishes shall be considered as per COSHH. • Adequate ventilation shall be provided, backed up respiratory protective equipment if necessary; local extraction ventilation may be required. • When using naked flames for paint removal, flame retardant overalls shall be worn. 	Staff
		Line Manager
		Team Leader
		Staff
Asphyxia / Poisoning	<ul style="list-style-type: none"> • Barrier cream or nitrile gloves shall be used to protect skin and overalls shall be worn to protect the rest of the body. • Adequate hygiene facilities shall be provided, including suitable skin cleaners and hot or warm water. • Workers shall not eat, drink or smoke in the painting area or in other areas where their hands are contaminated by paint. • If other contractors are on site, internal paint spraying shall be conducted out of hours or when other workers are not in the vicinity. • If old lead based paints are to be disturbed/removed then appropriate measures shall be implemented to reduce risk from lead content – <ol style="list-style-type: none"> Isolate area Keep dust to a minimum Water spray area to keep dust to a minimum Wear disposable overalls, face mask and safety glasses • See Risk Control Sheet NR/L3/MTC/RCS0216/PRO07 – Lead Work 	Staff
		Line Manager
		Staff
		Team Leader
Falling Materials	<ul style="list-style-type: none"> • Restricted areas and safe distances shall be established. • Debris shall be cleared at regular intervals. • Measures shall be taken to protect the Public (Cone off, secure area and post warning notices). 	Team Leader
		Staff
		Team Leader



Documents

Document Sharing Hub

Task Risk Control Sheet

Task Risks	Controls	Implemented By
Falls from height	<ul style="list-style-type: none"> All Portable Ladders shall be lashed or footed. Erection and use of Mobile elevated work platforms (MEWPs) shall be carried out by competent personnel – see relevant risk control sheet for Scissor/Boom NR/L3/MTC/RCS0216/MP09 or 10 See Risk Control Sheet NR/L3/MTC/RCS0216/GH04 – Working at Height – Section C Portable Ladders, D Portable Scaffold and E Mobile Elevated Working Platform. 	Staff Team Leader
Slips, Trips and Falls	<ul style="list-style-type: none"> See Risk Control Sheet NR/L3/MTC/RCS0216/GH02 – Underfoot Conditions. 	Team Leader

PPE Required by NR / Maintenance Policy

 Wear Head Protection	 Wear Foot Protection	 Wear Hi Visibility Clothing	 Wear Safety glasses to BS EN 166.F <p>If safety glasses introduce a risk (ie weather conditions) then the Team Leader shall assess the risk. The outcome of the assessment shall be recorded on the SSOWPS pack and safety glasses may be removed. This does not supersede the requirements for eye protection detailed on relevant Task Risk Control Sheets.</p>
--	--	---	--

Additional PPE Required by Task Risk Control Sheet

 Wear Hand Protection	 Wear Safety glasses to BS EN 166.F	 Wear Dust Mask	 Wear Safety Harness	 Wear Disposable Overalls		
---	---	---	--	---	--	--