

Task Risk Control Sheet

Working on Ground Frames

RCS No: NR/L3/MTC/RCS0216/SIG08
Issue: 2

Key Risks !

- Injury of body parts
- Contact with oils and greases
- Buried Services
- Electrocution DC

Personnel Involved

E&P	
S&T	✓
P/Way	
Off Track	
Property	

Tools / Equipment

Various Hand Tools
Chemicals /Lubricants as per SMS

Plant

Key Risks	Controls	Implemented By
General Hazards	<ul style="list-style-type: none"> • Set up a safe system of work • See Risk control Sheet NR/L3/MTC/RCS0216/GA01 – Work On or Near The Line • See Risk control Sheet NR/L3/MTC/RCS0216/GH02 – Underfoot Conditions • See Risk control Sheet NR/L3/MTC/RCS0216/GH01 – Manual Handling • See Risk control Sheet NR/L3/MTC/RCS0216/GH03 – Biological and Chemical Hazards 	COSS Team Leader / All Staff
Electrocution	<ul style="list-style-type: none"> • See Risk Control sheets NR/L3/MTC/RCS0216/GA20 Working Adjacent to DC Electrified Rails Risk Level 1- 5, • See Risk Control Sheet NR/L3/MTC/RCS0216/GA21 - Working Near Electrical Overhead Line Equipment • You and any tools or equipment you are carrying/using, shall be at least 2.75m (9 Feet) from the OLE unless an isolation has been arranged and a form C has been issued and available on site with the nominated competent COSS • Or you are working within the confines of a cage or suitable protection arrangements. 	Team Leader/ COSS/ All Staff
Injury of body parts	<ul style="list-style-type: none"> • Hand protection when required. • When lowering objects keep all body parts clear • Body parts, loose clothing jewellery shall be kept clear of moving parts 	Team Leader / All Staff
Contact with oils and greases	<ul style="list-style-type: none"> • Comply with data sheet requirements • Hand protection – gloves and/or barrier creams 	Team Leader / All Staff

Task Risk Control Sheet

Key Risks	Controls	Implemented By
Buried Services	<ul style="list-style-type: none"> All ground disturbance shall be planned Area shall be Cat Scanned by a competent person prior to the work and hazards identified and marked Permit to dig shall be issued and available on site Safe digging practice shall be adopted See Risk control Sheet NR/L3/MTC/RCS0216/GA08 - Ground Penetration and Excavations See Risk control Sheet NR/L3/MTC/RCS0216/SP05 - Use of Cable Avoidance Tool (C.A.T.) 	Planner / Team Leader / Competent Person

PPE Required by NR / Maintenance Policy



Wear Head Protection



Wear Foot Protection



Wear Hi Visibility Clothing



Wear Safety glasses to BS EN166.F

If safety glasses introduce a risk (ie weather conditions) then the Team Leader shall assess the risk. The outcome of the assessment shall be recorded on the SSOWPS pack and safety glasses may be removed.

This does not supersede the requirements for eye protection detailed on relevant Task Risk Control Sheets.

Additional PPE Required by Task Risk Control Sheet



Wear Hand Protection

--	--	--	--	--	--	--