

# Infrastructure Plant Manual

## Module P508 Mobile elevating work platforms

Technical content authorised by:

Edward Davison, Senior Policy Development Specialist [Plant and T&RS] | 02/03/2013

Technical content endorsed by:

James Allenden, Professional Head [Plant and T&RS] | 02/03/2013

Accepted for publication by:

Mick McManus, National Standards Manager | 02/03/2013



## Contents

|                                                                  |   |
|------------------------------------------------------------------|---|
| 0.1 Job roles                                                    | 3 |
| 0.2 Risk mitigation                                              | 3 |
| 1 Planning the work                                              | 4 |
| 1.1 Selecting the right machine                                  | 4 |
| 1.2 Installing materials or equipment                            | 4 |
| 1.3 Assessing the load                                           | 5 |
| 2 Safe system of work                                            | 6 |
| 2.1 General principles of operation                              | 6 |
| 2.2 Before starting work                                         | 6 |
| 2.3 When working                                                 | 6 |
| 3 Emergency and rescue procedure                                 | 7 |
| 4 Fitting additional equipment to a MEWP                         | 7 |
| 5 Maintenance and thorough exam                                  | 7 |
| 6 Work restraint anchor points on MEWPs                          | 8 |
| 7 Exiting the work platform away from stowed position            | 8 |
| Table 1 – Example assessments when loading a MEWP work platform. | 5 |

## 0.1 Job roles

This module is applicable to the following job roles, you must familiarise yourself with all of the clauses contained within it to understand your personal responsibilities. If you intend to carry out any of these roles you must hold the relevant Sentinel competency:

- Machine Controller
- Machine Operator
- COSS
- ES
- Planner
- Maintainer/Fitter
- Linesman (or other non machine operator/controller personal)
- Plant Operator License Holders
- Machine manufacturer
- Machine converter

## 0.2 Risk mitigation

This module helps mitigate the following high level risks:

- a) compliance with legislation (LOLER, PUWER, HASAW);
- b) runaway/failure to stop on demand, e.g. OTP running away on a gradient.
- c) MEWPs becoming out of control, e.g. MEWP operator being crushed under a structure;
- d) damage to assets, e.g. RRV or its load hitting a passing train during ALO operation;
- e) overturning, e.g. RRV overturning during lifting operations;
- f) collision, e.g. collision between a RRV and an OTM;
- g) staff injuries, e.g. Operator being trapped between machine and infrastructure or machine and machine.