

Infrastructure Plant Manual

Module P701 – On-track plant maintenance

Technical content authorised by:

Edward Davison, Senior Policy Development Specialist [Plant and T&RS] | 02/03/2013

Technical content endorsed by:

James Allenden, Professional Head [Plant and T&RS] | 02/03/2013

Accepted for publication by:

Mick McManus, National Standards Manager | 02/03/2013



Contents

0.1 Job roles	3
0.2 Risk mitigation	3
1 Vehicles with rubber tyres	4
2 Road-rail vehicle brake tests	4
2.1 Process flow chart	4
2.2 Test method	5
2.3 Test conditions	5
2.4 Routine maintenance brake test	5
2.5 Reference brake test	6
3 Trailer and attachment brake tests	7
3.1 Trailer or attachment parking brake test	7
3.2 Push pull brake test	8
3.3 Trailer or attachment service brake test	8
4 Rail wheels	8
Table 1 – Example of tabular calculation of maximum stopping distance	7
Table 2 – Trailer or attachment push pull test	8

0.1 Job roles

This module is applicable to the following job roles, you must familiarise yourself with all of the clauses contained within it to understand your personal responsibilities. If you intend to carry out any of these roles you must be competent to do so:

Maintainer/Fitter
Plant Supplier

0.2 Risk mitigation

This module helps mitigate the following high level risks:

- a) compliance with legislation (LOLER, PUWER, HASAW);
- b) runaway/failure to stop on demand, e.g. OTP running away on a gradient;
- c) collision, e.g. collision between a RRV and an OTM;
- d) damage to assets, e.g. RRV or its load hitting a passing train during ALO operation;
- e) derailment, e.g. trailer being loaded incorrectly;
- f) staff injuries, e.g. Operator being trapped between machine and infrastructure or machine and machine.