

# SSI Applications Group

## Approved Discussion Document

---

### DIS165

## Set to Work and Cross Boundary Best Practice

### Issue 6

Authors:

P Matthews and J Cooper, Signalling Solutions Ltd.



Approved by:

\_\_\_\_\_  
Chairman, SSI Applications Group

This document contains 8 pages and was approved by SSIAG at its meeting of 16/02/2011.

This document forms SSIAG's interim guidance on this topic pending the production of an update to the relevant chapter(s) of the SSI Applications Manual.

#### Distribution: (this issue only)

M Twigg  
W Billett  
A Elvins  
A C Dumbill  
S Taylor  
K Ireland  
P Matthews  
N T Smith  
J Cooper  
S Willis  
Chairman and Secretary  
A Hunt  
N Thomson  
S Crocker  
L Twigg

Network Rail, Manchester  
Network Rail, London  
Network Rail, London  
DeltaRail Group, Derby  
Atkins Rail, Birmingham  
Invensys Rail, York  
Signalling Solutions, Derby  
Invensys Rail, Chippenham  
Signalling Solutions, Birmingham  
Invensys Rail, Chippenham  
Lloyd's Register Rail, Derby  
SCSWG Secretary, Network Rail  
SPG Secretary, Network Rail  
Network Rail STPE, Birmingham  
Network Rail, York

This page is intentionally blank.

## SSI Applications Group

# SSIAG DIS165

## Set to Work and Cross Boundary Best Practice

### 1 DOCUMENT STATUS

This document has been prepared for the SSI Applications Group (SSIAG) and was approved subject to minor comments, now incorporated, on March 11<sup>th</sup> 2010.

Issue 5 was amended at SSIAG on 19/01/2011.

Issue 6 was amended and approved for generic application at SSIAG on 16/02/2011.

### 2 TABLE OF CONTENTS

|                                                            |                                                                          |          |
|------------------------------------------------------------|--------------------------------------------------------------------------|----------|
| <b>1</b>                                                   | <b>DOCUMENT STATUS .....</b>                                             | <b>1</b> |
| <b>2</b>                                                   | <b>TABLE OF CONTENTS.....</b>                                            | <b>1</b> |
| <b>3</b>                                                   | <b>INTRODUCTION.....</b>                                                 | <b>1</b> |
| <b>4</b>                                                   | <b>SET TO WORK .....</b>                                                 | <b>1</b> |
| <b>5</b>                                                   | <b>CROSS BOUNDARY .....</b>                                              | <b>2</b> |
| 5.1                                                        | Interface Design .....                                                   | 2        |
| 5.2                                                        | Design Process .....                                                     | 2        |
| 5.3                                                        | Completion Of CISR.....                                                  | 4        |
| 5.4                                                        | External Interfaces With Other Interlockings .....                       | 4        |
| <b>6</b>                                                   | <b>RECORDS OF DESIGN, PRODUCTION CHECK AND INDEPENDENT CHECKING.....</b> | <b>5</b> |
| <b>7</b>                                                   | <b>DATA TESTING .....</b>                                                | <b>5</b> |
| <b>APPENDIX A INTERLOCKING SET TO RUN CHECK LIST .....</b> |                                                                          | <b>6</b> |
| <b>APPENDIX B CROSS BOUNDARY CHECK LIST.....</b>           |                                                                          | <b>7</b> |

### 3 INTRODUCTION

This document proposes a more robust process for the “Set to Work” and “Cross Boundary” design by promoting discussion within SSI AG, with its final version being mandated by Network Rail for designers and checkers involved with the production of SSI, and SSI derivative data.

The paper is split into two sections addressing “Set To Work” and “Cross Boundary”.

### 4 SET TO WORK

The “Set to Work” is neither a principles test nor a control table test, and whilst it may be useful to have the control tables available, e.g. to check if there are any unusual controls that may be preventing a signal from clearing, they are not necessarily an inherent part of the “Set to Work”.