



National Aeronautics and
Space Administration

John C. Stennis Space Center
Stennis Space Center, MS
39529-6000

SSTD-8070-0115-MISC Rev. A
JULY 2017

COMPLIANCE IS MANDATORY

John C. Stennis Space Center OFFICE TRAILER TIE-DOWNS, BLOCKING AND ELECTRICAL CONNECTIONS

Approved by:

<u>Thom Rich</u>	<u>7/6/2017</u>
NASA SSC Center Operations	Date
Design & Construction Project	
Management Division	

Concurrence by:

<u>M. Killam</u>	<u>7/6/2017</u>
NASA SSC Center Operations	Date
Operations and Maintenance Division	

Issued by:

<u>ISSUED CEF</u>	<u>7/7/2017</u>
Central Engineering Files	Date

This is an uncontrolled document when printed. Verify that the document is current before use.

Documents
Document Sharing Hub

Stennis Standard	SSTD-8070-0115-MISC	A
	<i>Number</i>	<i>Rev.</i>
	Effective Date:	July 10, 2017
	Review Date:	July 10, 2022
Page 2 of 13		
Responsible Office: SSC COD Design & Construction Project Management Division		
SUBJECT: Office Trailer Tie-downs, Blocking & Electrical Connections		

Document History Log

Change/ Revision	Change Date	Originator/ Phone	Description
Basic	07.18.2012	B. Clarke, ext. 8-1645	Initial release, supersedes NSTL 97-016
Basic-1	02.11.2016	Carol Wolfram, ext. 8-1164	Administrative changes. Replaced “FOSC” with “SACOM” throughout document. Replaced “SWR” with “Task Order” throughout document.
A	07.10.2017	K. King, Ext 8-2682	Five-year review. Updated cover sheet to reflect approval by NASA SSC PMD, with concurrence by NASA SSC OMD. Administrative changes throughout document. Updated references and acronyms.

This is an uncontrolled document when printed. Verify that the document is current before use.

Stennis Standard	SSTD-8070-0115-MISC	A
	<i>Number</i>	<i>Rev.</i>
	Effective Date:	July 10, 2017
	Review Date:	July 10, 2022
Page 3 of 13		
Responsible Office: SSC COD Design & Construction Project Management Division		
SUBJECT: Office Trailer Tie-downs, Blocking & Electrical Connections		

Table of Contents

1.0	PURPOSE	4
2.0	APPLICABILITY	4
3.0	REFERENCES.....	4
4.0	RESPONSIBILITIES	4
5.0	BLOCKING SUPPORTS.....	5
5.1	General	5
5.2	Blocking Types	5
6.0	ANCHORS.....	5
6.1	Anchor Rods	5
6.2	Acceptable Anchor Types.....	5
6.3	Installation.....	6
6.4	Standard Method.....	6
7.0	TIE-DOWNS	6
7.1	Site preparation	6
7.2	General.....	6
8.0	ELECTRICAL CONNECTIONS	8
8.1	Power	8
8.2	Feeder Capacity	8
8.3	Fused Disconnect Switch.....	8
8.4	Breaker Panel	8
8.5	Grounding	8
8.6	Trailer Frame Grounding	9
9.0	RECORDS AND FORMS.....	9
10.0	DEFINITIONS	9
11.0	ACRONYMS AND ABBREVIATIONS.....	10
Appendix A: Typical Block Support And Tie-down Detail		11
Appendix B: Typical Trailer Tie-Down.....		12
Appendix C: Electric Power And Grounding Connection.....		13

This is an uncontrolled document when printed. Verify that the document is current before use.

Stennis Standard	SSTD-8070-0115-MISC	A
	<i>Number</i>	<i>Rev.</i>
	Effective Date:	July 10, 2017
	Review Date:	July 10, 2022
Page 4 of 13		
Responsible Office: SSC COD Design & Construction Project Management Division		
SUBJECT: Office Trailer Tie-downs, Blocking & Electrical Connections		

1.0 PURPOSE

This John C. Stennis Space Center (SSC) standard (SSTD) defines the Wind Zone II tie-down requirements and electric power connections for manufactured housing, trailers, or other temporary enclosures at SSC.

2.0 APPLICABILITY

This SSTD applies to all National Aeronautics and Space Administration (NASA) SSC contractors, subcontractors or other personnel involved in the set-up or use of manufactured housing, trailers or other temporary enclosures.

3.0 REFERENCES

All references are assumed to be the latest version unless otherwise indicated.

24 CFR Section 3280, *Federal Manufactured Home Construction and Safety Standards*
 ASCE 7, *Minimum Design Loads for Buildings and Other Structures*
 International Residential Code (IRC) *for One and Two Family Dwellings*
 MH-2009-1, *Mississippi Department of Insurance "Manufactured Home Installation Inspection Program"*
 Southern Building Code Congress International (SBCCI), *Southern Building Code*
 SPR 1440.1, *SSC Records Management Program Requirements*
 SCWI-8715-0003, *SSC Fall Protection Program*
 SSTD-8070-0005-CONFIG, *SSC Preparation, Review, Approval, and Release of SSC Standards*
 SSTD-8070-0119-MISC, *SSC Dig Permit Standard (Form SSC-618)*

4.0 RESPONSIBILITIES

- a. Users of this SSTD shall comply with its requirements, ensure use of the correct version of this SSTD and the documents it references, and inform the appropriate organization of needed changes in accordance with SSTD-8070-0005-CONFIG.
- b. Responsibilities for the use and control of this SSTD and for the review and approval of revisions or cancellation of this SSTD shall be as specified in SSTD-8070-0005-CONFIG and the applicable documents referenced therein.