

Subject 2196

June 22, 2018

SUMMARY OF TOPICS

The following topic for the Standard for Fire Test for Circuit Integrity of Fire-Resistive Power, Instrumentation, Control and Data Cables, UL 2196, is being recirculated:

1. Revision to provide clarification to the Hose Stream Test requirement

COMMENTS DUE: JULY 23, 2018

For your convenience in review, proposed additions to the previously proposed requirements dated (2018-02-23) are shown underlined and proposed deletions are shown ~~lined-out~~.

1. Revision to provide clarification to the Hose Stream Test requirement

RATIONALE

Responses to comments have been posted within the UL 2196 Proposal Review Work Area dated (2018-02-23).

PROPOSAL

5.2 HOSE STREAM TEST

5.2.1 Test Assembly

5.2.1.1 The hose stream test shall be conducted no longer than 5 minutes after the fire exposure test and shall be conducted on the test assembly. The cable shall not be energized during the hose stream test. See Clause 6.2.1.

5.2.1.2 The hose stream test shall be conducted in accordance with the requirements in CAN/ULC-S101, Standard Methods of Fire Endurance Tests of Building Construction and Materials, or ANSI/UL 263, Standard for Fire Tests of Building Construction and Materials. ~~See Clause 6.2.1.~~

Copyright © Underwriters Laboratories Inc.

**UL COPYRIGHTED MATERIAL –
NOT AUTHORIZED FOR FURTHER REPRODUCTION OR
DISTRIBUTION WITHOUT PERMISSION FROM UL**



Documents

Document Sharing Hub

No Text on This Page